



SPECIFICATION OF PRODUCT 承认书

CUSTOMER:		
DESCRIPTION:	SMD Piezo Buzzer	
ILOSAM P/N:	ISP-2311	
CUSTOMER P/N: _		
DATE:	2018-8-28	

CUSTOMER	APPROVER	CHECKER
	Yunqing Wu	Bing Yan

ILOSAM ELECTRONICS CO.,LTD.

906-907 ROOM,184 GASAN DIGITAL 2ROAD,GUEMCHUN-GU,SEOUL,KOREA

TEL:82-2-2615-0158

FAX:82-2-2615-1043


SITE: WWW.ILOSAM.COM



1.SPECIFICATION 规格

No.	Item	Unit	Specification	Condition
1	Oscillation Frequency	Hz	4000	square wave
2	Operating Voltage	Vp-p	1~30	
3	Rated Voltage	Vp-p	9	
4	Current Consumption	mA	MAX. 9	at Rated Voltage
5	Sound Pressure Level	dB	MIN. 100	at 10cm at Rated Voltage
6	Electrostatic Capacity	pF	19000±30%	at 100Hz 1V
7	Operating Temperature	$^{\circ}\!\mathbb{C}$	-30 ~ +85	
8	Storage Temperature	$^{\circ}\!\mathbb{C}$	-40 ~ +90	
9	Dimension	mm	Ф23x H11	See appearance drawing
10	Weight (MAX)	gram	4	
11	Housing Material		PPS(Black)	
12	Leading Pin		Tin Plated Brass(AU)	See appearance drawing
13	Environmental Protection Regulation		RoHS	

2. APPEARANCE DRAWING 尺寸图



Tol: ± 0.3 Unit: mm


3.TESTING METHOD 测量方式

Standard Measurement conditions


Temperature:25±2°C Humidity:45-65%

Acoustic Characteristics:


The oscillation frequency, current consumption and sound pressure are measured by the measuring instruments shown below.



In the measuring test, buzzer is placed as follows:




4. Typical Frequency Response Curve



5. Soldering Condition

(1)Recommendable reflow soldering condition is as follows (Reflow soldering is twice)

Note: It is requested that reflow soldering should be executed after heat of product goes down to normal.



Heat resistant line

(Used when heat resistant reliability test is performed)

(2)Manual soldering

Manual soldering temperature 350 °C within 5 sec.

6. RELIABILITY TEST

NO.	ITEM	TEST CONDITION AND REQUIREMENT		
1	High Temperature Test (Storage)	After being placed in a chamber with 80 2°C for 96 hours and then being placed in normal condition for 2 hours. Allowable variation of SPL after test: 10dB.		
2	Low Temperature Test (Storage)	After being Placed in a chamber with -30 2°C for 96 hours and then being placed in normal condition for 2 hours. Allowable variation of SPL after test: 10dB.		
3	Humidity Test	After being Placed in a chamber with 90-95% R.H. at 40 2°C for 96 hours and then being placed in normal condition for 2 hours. Allowable variation of SPL after test: 10dB.		
4	Temperature Cycle Test	The part shall be subjected to 5 cycles. One cycle shall be consist of: +70°C +25°C +25°C -20°C -20°C		
5	Drop Test	Drop on a hard wood board of 4cm thick, any directions ,6 times, at the height of 75cm. Allowable variation of SPL after test: 10dB.		
6	Vibration Test	After being applied vibration of amplitude of 1.5mm with 10 to 55 Hz band of vibration frequency to each of 3 perpendicular directions for 2 hours. Allowable variation of SPL after test: 10dB.		
7	Solderability Test	Lead terminals are immersed in rosin for 5 seconds and then immersed in solder bath of +300 5°C for 3 1 seconds . 90% min. lead terminals shall be wet with solder (Except the edge of terminals).		
8	Terminal Strength Pulling Test	The force of 9.8N(1.0kg) is applied to each terminal in axial direction for 10 seconds. No visible damage and cutting off.		

TEST CONDITION.

 Standard Test Condition
 : a) Temperature: +5 ~ +35℃
 b) Humidity: 45-85%
 c) Pressure: 860-1060mbar

 一般测试条件
 : a) 温度: +5 ~ +35℃
 b) 湿度: 45-85%
 c) 气压: 860-1060mbar

 Judgment Test Condition
 : a) Temperature: +25 ± 2℃
 b) Humidity: 60-70%
 c) Pressure: 860-1060mbar

 争议时测试条件
 : a) 温度: +25 ± 2℃
 b) 湿度: 60-70%
 c) 气压: 860-1060mbar

7. PACKING STANDARD ø330 1 Reel: 300 PCS 8.0 50 **ø**23 24 Carton Box 28±0.1 (6 Inner Box) Inner Box (1Layer Reel) Inner Box 330mmx330mmx40mm 1x300PCS=300PCS Carton Box 350mmx350mmx370mm 6x300PCS=1800PCS